

IMPORTANT


JEEP JL/JT GEARSHIFT CABLE ADJUSTMENTS – IF NEEDED

CAUTION: When replacing the clutch, it is recommended to leave the shift cables and bracket attached to the transmission – please read ALL instructions prior to clutch replacement. The Shift cable bracket should not be removed from the transmission unless rebuilding of transmission and access to the detent plugs is required. IF the shift cable bracket has been removed from the transmission, you **MUST** perform the shift cable reset procedure as outlined below: This step is critical. If not set correctly, hard shifting and/or transmission damage is possible.

NOTE: The shift cable adjustment device is located under the center console at the shifter

If the shift cables and bracket remain in place during the clutch installation, the shift cable reset procedure is usually not necessary, however this procedure can be performed at any time as needed if gear selection becomes difficult.

1. THE ENGINE MUST BE OFF for the duration of this procedure.
2. Remove shift cable access door from the passenger side of the center console.
3. From the driver's seat, depress the clutch pedal and then move the shift lever to the 3rd gear position. Leave the transmission in 3rd gear, Jiggle the shifter side to side and then release the shift knob, letting the shifter spring center the shift lever.
4. Re-engage the clutch. **DO NOT** bump or move the shifter.
5. Locate the shifter cable adjuster under the console just to the right side of the shifter assembly.
6. Release the adjuster by pushing the locking tab (1) outward.
7. The cable will automatically reposition. Next depress the locking tab (1) to lock the adjuster in place.
8. Verify that the shifter operates properly.
9. Reinstall the shift cable access door and test drive vehicle.



Should you have questions or if you need further information, please call our tech line at (928) 771-8422 or visit us at www.centerforce.com